

**SPARE PARTS**

**RBA Code Number**  
RBA8900-999-002

**Part Description**  
Replacement cartridge

**TROUBLE SHOOTING**

PROBLEM	POSSIBLE CAUSES	SOLUTION
No flow or low volume	Water turned off. Inlet strainer blocked.	Turn on. Remove and clean.
Water flows continuously	Cartridge blocked with dirt or cartridge damaged	Remove and clean. Replace the cartridge*
Leak under knob	Loose screws or cartridge damaged	Tighten brass screw under white flow adjustment screw. Replace the cartridge*
Short or long flow stream	Low or high pressure	Rectify supply pressure as per hydraulic requirements
Short or long flow stream	Cartridge adjustment required	Remove button, adjust white screw in cartridge clockwise to reduce, or counter clockwise to increase.

\*Replacement Cartridge Model RBA8900-999-002

**Note:** This product should be installed, by suitably qualified persons, in a fit for purpose application, to suitable materials, using suitable fixings and comply with any relevant codes. It should be inspected periodically for signs of wear and tear that may affect performance or safety.

Dimensions are subject to manufacturer's tolerance of +/-10mm. Rough-in should be completed with each fixture.

**Important:** Installation Instructions are subject to change without notice.

Please visit [www.rba.com.au](http://www.rba.com.au) for latest revision.



**RBA8901-102**

WALL MOUNTED DRINKING FOUNTAIN



Model	RBA8901-102
Date	10/03/20
Doc#	ii/ RBA8901-102/0320

Supersedes all previous

